



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
9-29-80
SEP 29 1980

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Geo. Bennett of Wooden Petroleum Co. has this date requested permission to plug the following described well:

Mr. Bennett guarantees payment of the plugging fee.

Operator's full Name: Wooden Petroleum Co.

Complete Address: P.O. Box 996 Hays, Kans. 67601

Lease Name: Berland Well No. #16-A"

Location: NW-SW-NW Sec. 19 Twp. 10⁵ Rge. 19 (E)(W) W

County: Rooks Total Depth 3778' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bennett was instructed to plug the well as follows:

10 3/4" 295' SR. CUC w/ 1300' Omt. - 7" Set @ 3775' - CUC.
Ordered 7 yds. Ready mix - 1 1/2 Bbl's Sand +
1 Bbl. Gravel + Rocks. for bridge @ approx 1000 ft.
Put 2 1/2 Bbl's Sand and 2 yd. Ready mix in Bottom, Load hole.
and build 45' Rock + Gravel bridge at approx 1000 ft.
Put in 6 1/2 yds Ready mix.
Returned on Sept 26th and filled 7" casing to
cellar w/ 1 yd. Ready mix.

Very truly yours,

Marion Schmidt
Conservation Division Agent

By allied Ready Mix (Hays)