

15-163 - 02679 - 0000  
R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 145-7

LOCATION NE NE NW

SEC. 19 TWP. 10 RGE. 19

Dry Hole S.W.D. Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 14 Lease Berland

Operator Skelly Oil Co Address \_\_\_\_\_

Field Berland County Rooks

Total Depth 3860 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1630', circulated with cement - 5 1/2" at 3799  
with 100 sax cement behind.

Lane-wells plugs to 3741', perforations at 3520',

Filled hole with chat and mud 3741' to 3500', set rock

bridge and 5 sax cement with dump bailer, pulled 2985', of

5 1/2", mudded hole to 250', set rock bridge and 15 sax cement,

filled with heavy mud to 35', set rock bridge and 10 sax

cement to bottom cellar.

**PLUGGING**  
FILE SEC. 19 TWP. 10 RGE. 19  
BOOK PAGE 145 LINE 7

4-11-50

*J. P. Letty*  
District Conservation Agent

Date 4-5-50