

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1

March 2009

This Form must be Typed

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 30483

Name: Kremeier Production & Operating

Address 1: 3183 Us Hwy 56

Address 2: \_\_\_\_\_

City: herington State: ks Zip: 67449 + \_\_\_\_\_

Contact Person: Chris Kremeier

Phone: ( 785 ) 366-6957

API No. 15 - 115-20,779 - 00 - 00

If pre 1967, supply original completion date: \_\_\_\_\_

Spot Description: \_\_\_\_\_

NW-SE-SW.      Sec. 6 Twp. 19 S. R. 4  East  West

990 Feet from  North /  South Line of Section

1,320 Feet from  East /  West Line of Section

Footages Calculated from Nearest Outside Section Corner:

NE  NW  SE  SW

County: Marion

Lease Name: Jirak A KCCP Well #: 1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_

SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: none Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 200 feet Cemented with: \_\_\_\_\_ Sacks

Production Casing Size: 4 1/2 Set at: 2398 Cemented with: \_\_\_\_\_ Sacks

List (ALL) Perforations and Bridge Plug Sets:

2246 to 62

Elevation: 1369 ( G.L. /  K.B.) T.D.: 2400 PBTD: 2398 Anhydrite Depth: Miss

(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_

(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

set cement plug from bottom to 2000", shoot pipe off and pull. Set cement plug from 300' to surface.  
Let set, top off if needed.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

didn't drill well

RECEIVED

SEP 24 2009

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Kremeier Production & Operating

Address: 3183 US US Hwy 56 City: Herington State: KS Zip: 67449 + \_\_\_\_\_

Phone: ( 785 ) 258-2321

Plugging Contractor License #: 30483 Name: Kremeier Production & Operating

Address 1: \_\_\_\_\_ Address 2: \_\_\_\_\_

City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_ + \_\_\_\_\_

Phone: ( \_\_\_\_\_ ) \_\_\_\_\_

Proposed Date of Plugging (if known): Nov. 1 2009 if dry

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9-23-09 Authorized Operator / Agent: [Signature]

(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Diast 2*

JAY ENERGY DEVELOPMENT CORP  
 BOX 1097 124 S MAIN #1 "A" GIRAK 6-19-4E  
 HESSTON KS 67062 NW SE SW  
 CONTR KS DRILG & WELL SVC CTY MARION

GEOL \_\_\_\_\_ FIELD LOST SPRINGS

E 1377 KB CM 8/5/81 CARD ISSUED 2/18/82 IP P 5 BO & 95 BWPD &  
 1369 GL 55 MCFGPD  
 API 15-115-20,779 MISS 2346-62 OA

+	+
+	+
+	+

SMP	TOPS	DEPTH	DATUM
MISS CHT	2338	-	961
RTD	2400	-	1023
NO LOG			
LKC	1799		

8-5/8" 200, 4 1/2" 2398  
 NO LST'S  
 MICT - CO, PF (MISS) B/2346-50, 20/  
 2352-62, AC 1000G (15%), FRAC 50,000#  
 SD & 5600BW, POP, P 5 BO & 95 BWPD &  
 22 MCFGPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

RECEIVED  
 SEP 24 2009  
 KCC WICHITA



CORPORATION COMMISSION

Mark Parkinson, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

• KREMEIER, LES DBA KREMEIER PROD. AND OPER. CO.  
3183 US HWY 56  
HERINGTON, KS 67449-5000

October 01, 2009

Re: JIRAK A #1  
API 15-115-20779-00-00  
6-19S-4E, 990 FSL 1320 FWL  
MARION COUNTY, KANSAS

Dear Operator:

The purpose of this letter is twofold. First, this letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

This letter is also to notify you that during the central office's review of your CP-1 for license number verification, staff has discovered that you are not the current operator of record of the above well on file with the Conservation Division. **Central office staff is therefore requesting that you verify that you are the operator of record of the above well. The proper procedure for verifying operator authority is by filing a Conservation Division form T-1 (Request for Change of Operator; Transfer of Injection or Surface Pit Permit).** If a T-1 has already been filed with the Conservation Division reflecting the transfer of operator authority, please disregard this paragraph. If a T-1 has not been filed reflecting the transfer, please see the attached letter, which explains the T-1 filing process.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. Furthermore, this notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after March 30, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond

Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000