

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21349-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 11-25S-9W
2310 feet from S Section Line, 330 feet from W Section Line
Lease Name: BIGGERSTAFF Well #: 2-11
County: RENO Total Vertical Depth: 3997 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	187		190 sxs cmt
PROD	5.5	3963	2423	145 SXS CMT

129.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed
Plugging
Method:

SEE PER KCC RULES

Plugging Proposal Received By: SHANE JONES WitnessType: PARTIAL
Date/Time Plugging Completed: 08/24/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK ON 8/21/2009 TO 3800' & PLACE 5 SX OF CEMENT ON TOP OF SAND WITH BAILER. 8/24/2009 CUT 5.5 CASING OFF AT 2433' PULLED TO 1400' SPOTTED 50 SXS OF 6/40/4% WITH 3% CC. WAITED 1.5 HOURS AND TAGGED AT 1250'. PULLED CASING TO 805' SPOTTED 35 SXS OF CEMENT, PULLED TO 253' CIRCULATED TO SURFACE WITH 100 SXS OF CEMENT. 8/25/2009 TOP PLUG FELL BACK 45 FEET. 8/27/2009 TOPPED WITH 25 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
3850	3854	CSG	

INVOICED
DATE 10-1-09
INV. NO. 2010060314

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, KS. 60/40/4% GEL POS-MIX TICKET #32886

Plugged through: CSG

District: 02

Signed

B. J. HOPE

(TECHNICIAN)

PKT

VJK