

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20830-00-00
Spot: SWSENW Sec/Twnshp/Rge: 5-34S-6E
2928 feet from S Section Line, 3523 feet from E Section Line
Lease Name: COX Well #: 2-A
County: COWLEY Total Vertical Depth: 2194 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	155		125 SX
PROD	5.5	2186	924	150 SX

71.31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2009 2:00 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO LLC Phone: (620) 218-1822

Proposed Plugging Method: PER KCC REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2009 10:30 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1,800', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 924', LAYED DOWN 29 JTS 5-1/2" CASING. RIH W/TBG @ 325'. CONSOLIDATED MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-6-2009 @ 10:30 AM. CONSOLIDATED CEMENT TICKET #20895.

Perfs:

Top	Bot	Thru	Comments
1960	1996	CSG	
1943	1953	CSG	
1940	1943	CSG	

INVOICED
DATE 10-1-09
INV. NO. 2010060315
RECEIVED
AUG 28 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

14

PKT