

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21856-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 5-34S-6E
2231 feet from S Section Line, 5221 feet from E Section Line
Lease Name: WALDSCHMIDT A TWIN Well #: 3
County: COWLEY Total Vertical Depth: 2951 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	131		75 SX
PROD	5.5	2950		250 SX

95.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2009 2:00 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO Phone: (620) 218-1822

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2009 5:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SET CIBP @ 1,630', DUMP BAILED 2 SXS CEMENT ON TOP. CUT CASING @ 964', LAYED DOWN 30 JTS 5-1/2" CASING. RIH W/TBG @ 350', CONSOLIDATED MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-10-2009 @ 5:30 PM. CONSOLIDATED CEMENT TICKET #23498.

Perfs:

Top	Bot	Thru	Comments
2925	2932	CSG	
1650	1654	CSG	

INVOICED
DATE 10-1-09
INV. NO. 2010060315

RECEIVED
AUG 28 2009
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT

14