

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21083-00-01
Spot: NWSESENE Sec/Twnshp/Rge: 35-20S-26W
3053 feet from S Section Line, 484 feet from E Section Line
Lease Name: GOODMAN OWWO Well #: 1
County: NESS Total Vertical Depth: 4432 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	365		WITH 250 SX CMT
DVT		1664		WITH 500 SX CMT <u>144.04</u>
PROD	4.5	4414	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2009 1:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND OFF AT 3627' & USE 5 SX CMT. RUN TBG TO 1690' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2009 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CASING WAS PARTED AT 3627'. COULD NOT GET BACK INTO. SANDED TO 3580' & 5 SX CMT. RUN TBG TO 1663' & FILLED CASING TO SURFACE WITH 100 SX CMT. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4412	4416		

INVOICED
DATE 10-1-09
INV. NO. 2010060317

RECEIVED
AUG 19 2009

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA

District: 01

Signed Michael Maier (TECHNICIAN)

RECEIVED

AUG 12 2009

KCC DODGE CITY

Form CP-279