

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20906-00-02
Spot: NESESW Sec/Twnshp/Rge: 34-15S-19W
982 feet from S Section Line, 3134 feet from E Section Line
Lease Name: DOERR Well #: 3
County: ELLIS Total Vertical Depth: 3649 feet

Operator License No.: 32875
Op Name: CWB - CO, A GENERAL PARTNERSHIP
Address: PO BOX 186
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1252	0	w/450 sxs cmt
PROD	5.5	3649	0	w/175 sxs cmt

118.59

Well Type: EOR UIC Docket No: E25750.1 Date/Time to Plug: 08/24/2009 10:00 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JAMES HERTEL Company: CWB - CO, A GENERAL PARTNERS Phone: (675) 650-3118

Proposed Plugging Method: Ordered 600 sxs 60/40 pozmix - 4% gel - 1000# hulls.
Junk in the hole at approximately 2200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2009 1:05 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1800' - 1250' - 550' - 150'.
Prairie Hawk Well Service RIH with tubing to 2187'.
Allied rigged to tubing - pumped 100 sxs neat cement - let set 15 minutes - pumped 150 sxs cement with 400# hulls mixed in.
Cement circulated up 5 1/2" casing. Shut in 5 1/2" casing.
Pulled tubing to 1200' - pumped 20 sxs cement - fluids started to circulate out 8 5/8" casing but plugged off.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 20 sxs cement to circulate up 8 5/8" casing. Shut in 8 5/8".
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3456	3509		LKC

INVOICED
DATE 10-6-09
INV. NO. 2010060300

RECEIVED
AUG 27 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37548.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3


AUG 24 2009

JET DRILLING CO., INC. &
 BILL J. PORTER #3 DOERR 34-15-19W
 514 ONE TWENTY BLDG. WICHITA, KS
 CONTR SHIELDS DRILLING CO., INC. CITY ELLIS

GEOL TOM WESSELOWSKI FIELD FLRU WEST

E 2045 KB C-7/5/73 CARD ISSUED 3/14/74 IP SWDW

API 15-051-20,906 LKC 3456-3509



LOG	TOPS	DEPTH	DATUM
ANH		1238	+ 807
B ANH		1281	+ 764
TOP		2995	- 950
HEEB		3282	-1237
TOR		3304	-1259
LANS		3327	-1282
BKC		3570	-1525
ARB		3628	-1583
REAG SD		3638	-1593
LTD		3648	-1603

8-5/8" 1252/450sx, 5 1/2" 3649/175sx

DST (1) (LANS) 3375-3405/15-30-30-30,
 30' WM, BHP 765-765#, FP 25-45#
 DST (2) (LANS) 3485-3535/15-30-30-30,
 5' M, BHP 1155-1077#, FP 35-45#
 DST (3) 3630-3638/15-30-45-45, 220'
 GIP, 100' OIL (GR 380), 100' MW,
 BHP 225-92#, FP 20-75#
 DST (4) 3637-3643/15-30-45-45, 120' W
 W/SSO, 1080' SULF WTR, BHP 1225-
 1225#, FP 45-585#
 CO 3653, FP (ARB 12/3629-32, FU 1850'
 FL (1 GAL FO, 400' RM REST WTR), BP
 3540, PF (LKC) 3/3456, 3/3487, 3/3509,
 A 1500, FU 2400' W + SC OIL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS