

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21245-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 17-23S-8W
4808 feet from S Section Line, 598 feet from E Section Line
Lease Name: KNOWLES TRUST Well #: 1-SWD
County: RENO Total Vertical Depth: 4379 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206		210 SX
PROD	5.5	4097	1980	150 SX COMMON <u>142.32</u>

Well Type: SWD UIC Docket No: D26793.0 Date/Time to Plug: 06/04/2009 8:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON Phone: (785) 483-1559

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 06/05/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3500', 5 SX PLACED ON TOP SAND. CASING RIPPED OFF AT 1980', PULLED CASING TO 1300' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 800' SPOTTED 35 SXS OF CEMENT WITH 3% CC WAITED 1.5 HOURS TAGGED CEMENT AT 745', PULLED CASING TO 270' AND CIRCULATED TO SURFACE WITH 155 SX OF CEMENT.

Perfs:

INVOICED
DATE 10-6-09
INV. NO. 20100 60324

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE, TICKET #31350. WELL PLUGGED DUE TO FAILED MIT.

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

14

PKY