

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20017-00-01  
Spot: SWSWNEW Sec/Twnshp/Rge: 7-35S-34W  
4030 feet from S Section Line, 3890 feet from E Section Line  
Lease Name: DOWDY OWWO Well #: 1-7  
County: SEWARD Total Vertical Depth: 6760 feet

Operator License No.: 32842  
Op Name: JMA ENERGY COMPANY, LLC  
Address: 1021 NW GRAND BLVD  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6220		WITH 2 SX CMT
CIBP		6391		
SURF	8.625	1405		WITH 700 SX CMT 219.70
PROD	4.5	6462	1517	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2009 8:30 AM

Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Rcvd. from: SONNY JOHNSTON Company: JOHNSTON OILFIELD SERVICES Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP @ 6250 & 2 SX CMT. PLUG AT 1430' WITH GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60-0' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/12/2009 5:00 PM

KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 6220' & 2 SX CMT. 1ST PLUG AT 1455' WITH 60 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. DID NOT CIRCULATE. FL @ 120'. 4TH PLUG TOPPED OFF 8 5/8" WITH 50 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
6334	6353		CHESTER SAND
6272	6278		MORROW

INVOICED

DATE 10-6-09  
INV. NO. 2010060333

KANSAS CORPORATION COMMISSION

AUG 24 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

RECEIVED

AUG 18 2009

KCC DODGE CITY

(TECHNICIAN)

Form CP-2A