

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23497-00-00
Spot: NESESW Sec/Twnshp/Rge: 34-8S-24W
1160 feet from S Section Line, 2200 feet from W Section Line
Lease Name: BROWN Well #: 1-34
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	214		150 SX

131.30

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/14/2009 4:15 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 628-3449

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 06/14/2009 6:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2125' w/25 sxs.
2nd. Plug at 1250' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED

DATE 10-6-09
INV. NO. 2010060323

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

RECEIVED
AUG 27 2009
KCC WICHITA

District: 04

Signed Case Morris
(TECHNICIAN)

AUG 26 2009

PRY