

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21222-00-00
Spot: SWSW Sec/Twnshp/Rge: 9-23S-8W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: WILKINSON Well #: 1
County: RENO Total Vertical Depth: 3800 feet

Operator License No.: 5316
Op Name: FALCON EXPLORATION, INC.
Address: 125 N MARKET STE 1252
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	369		250 SX
PROD	5.5	3775	1971	130 SX <u>23.50</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2009 8:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: LEON KUHN Company: FALCON Phone: (785) 483-1559

Proposed Plugging Method: PER KCC INSTRUCTION.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/01/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3610', TOPPED WITH 5 SXS OF CEMENT WITH BAILER. RIPPED CASING OFF AT 1971', PULLED CASING TO 1295' SPOTTED 35 SXS OF CEMENT CLASS A WITH 3% CC, WAITED 1.5 HOURS TAGGED CEMENT AT 1150'. PULLED CASING TO 797' SPOTTED 35 SXS OF CLASS A CEMENT, PULLED CASING TO 390' CIRCULATED TO SURFACE WITH 120 SXS OF CLASS A CEMENT.

Perfs:

Top	Bot	Thru	Comments
3674	3680	CSG	
3663	3665	CSG	
3655	3658	CSG	

INVOICED
DATE 10-6-09
INV. NO. 2010060324

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, KS TICKET #36310 CLASS A CEMENT USED, WITH CC

Plugged through: CSG

District: 02

Signed B. J. Hope
(TECHNICIAN)