

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22175-00-00
Spot: SESWSE Sec/Twnshp/Rge: 1-16S-28W
495 feet from S Section Line, 1485 feet from E Section Line
Lease Name: BENTLEY TRUST Well #: 34-1
County: LANE Total Vertical Depth: 4550 feet

Operator License No.: 34038
Op Name: FLATIRONS RESOURCES LLC
Address: 303 E 17TH AVE STE 940
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 252 WITH 175 SX CMT

147.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/03/2009 12:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY STRUTT Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2070' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: LINDLEY REIMER Witness Type: NONE
Date/Time Plugging Completed: 08/03/2009 2:45 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

1ST PLUG AT 2070' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE 10-6-09
INV. NO. 2010060326

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
AUG 19 2009
KCC WICHITA

District: 01

RECEIVED
AUG 12 2009
KCC DODGE CITY

Signed _____
(TECHNICIAN)