

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21188-00-00
Spot: NESESE Sec/Twnshp/Rge: 10-14S-10W
1017 feet from S Section Line, 439 feet from E Section Line
Lease Name: ERNEST SOUKUP Well #: 1-10
County: ELLSWORTH Total Vertical Depth: 3000 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	436	1860	225 SX CMT.
PROD	5.5	2998		150 SX CMT. <u>97.50</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2009 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/12/2009 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2800' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1860' AND PULL TO 1250' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 485' AND PUMP 35 SX'S CEMENT. PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT - CELLAR STAYED FULL. USED 175 SX'S CEMENT TOAL.

Perfs:

Top	Bot	Thru	Comments
2960	2964	CSG	
2952	2957	CSG	
2881	2901	CSG	

INVOICED
DATE 10-6-09
INV. NO. 2010060329

RECEIVED
AUG 20 2009
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-33047.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)