

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00790-00-01
Spot: SESESW Sec/Twnshp/Rge: 30-8S-16W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MCCOMB Well #: 2
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 32247
Op Name: CRAWFORD, JEFF DBA JEFF'S OILWEL
Address: 705 BAUM ST BOX 245
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	175	0	w/unknown sxs cmt
PROD	4.5	3398	0	w/unknown sxs cmt <u>110.50</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2009 3:30 PM
Plug Co. License No.: 32247 Plug Co. Name: CRAWFORD, JEFF DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: JEFF CRAWFORD Company: CRAWFORD, JEFF DBA JEFF'S OIL Phone: (785) 885-4570

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perforated at 2050' - 1740' - 800'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2009 7:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2250' - pumped 85 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1600' - pumped 50 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 1300' - pumped 75 sxs 60/40 pozmix - 4% gel with 250# hulls.
Pulled all tubing. Hooked onto 4 1/2" casing - pumped 25 sxs 60/40 pozmix - 4% gel to circulate 8 5/8" to surface.
Shut the 8 5/8" off and pumped 75 sxs 60/40 pozmix - 4% gel with 250# hulls.

Perfs:

Top	Bot	Thru	Comments
3254	3257		
3233	3237		
3224	3227		
3206	3209		
3150	3153		
3128	3132		
3083	3094		

INVOICED
DATE 10-6-09
INV. NO. 2010060332
RECEIVED
AUG 21 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET #037597.

KCC WICHITA

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

Form CP-2/3

AUG 18 2009

RYAN CONSOLIDATED

#2 McCOMB

30-8-16W
SE SE SW

Contr. BERGMAN DRILLING

ROOKS County

E 1898RBComm. Comp. 4/11/63 IP PMP 21 BOPD + 30%

W, GR 36/L/KC 3082-

SMP Tops	Depth	Datum
TOP	2783	-885
HEEB	3001	-1103
TOR	3024	-1126
LANS	3044	-1146
B/KC	3288	-1390
ARB	3372	-1474
TD	3400	-1502

Casing
8" 175:
WAS: M.P. SPRINGER, #1 MC COMB,
D & A 8/12/60:
DST 3083-92/2 HRS, 140' MO, 820'
GIP, BHP 1000#:
NEW INFO: CODD 3400: 4" 3398:
/3083-94: A 2500: /3254-57: A
2500: /3206-09: A 2500: /3224-
27: /3233-37: A 2500: /3150-53:
A 2500: /3128-32: A 2500: SWB 8
BFPH (20% OIL)/6 HRS: PB 3008:
4/1200: SQZD/400 SX: BP 3140:
SWB WTR (3128-32): SQZ: CO 3348:
HRABE SWB (ALL ZONES) 3 BFPH
(40% OIL):

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

GEOL-LEE CORNELL