

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20730-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 19-34S-34W  
329 feet from S Section Line, 4361 feet from E Section Line  
Lease Name: ROY GREEN Well #: 1-19  
County: SEWARD Total Vertical Depth: 7000 feet

Operator License No.: 32842  
Op Name: JMA ENERGY COMPANY, LLC  
Address: 1021 NW GRAND BLVD  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6200		WITH 2 SX CMT 227.50
CIBP		6400		
SURF	8.625	1722		WITH 830 SX CMT
COND	20	20		2 YDS READY MIX
PROD	5.5	6608	1770	WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2009 11:30 AM  
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES  
Proposal Rcvd. from: SAMMY JOHNSTON Company: JOHNSON OILFIELD SERVICES Phone: \_\_\_\_\_

Proposed Plugging Method: PLUG AT 1750' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2009 4:00 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 6200' & 2 SX CMT. 1ST PLUG AT 1755' WITH 60 SX CMT W/3% CC. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6456	6482		
6212	6224		UPPER CHESTER

INVOICED  
DATE 10-6-09  
INV. NO. 2010060334

KANSAS CORPORATION COMMISSION

AUG 24 2009  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: TBG

District: 01

RECEIVED

AUG 18 2009

KCC DODGE CITY

Signed

(TECHNICIAN)

Form CP 20