

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20712-00-00
Spot: NENESW Sec/Twnshp/Rge: 30-17S-10W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BECK Well #: 5
County: ELLSWORTH Total Vertical Depth: 3310 feet

Operator License No.: 7030
Op Name: JOHN ROY EVANS OIL COMPANY LLC
Address: 405 FOURTH ST BOX 385
CLAFLIN, KS 67525

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 261 | | 200 SXS |
| PROD | 4.5 | 3310 | | |

107.58

Well Type: OIL UIC Docket No: 3004 Date/Time to Plug: 08/19/2009 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: Classic Well Service Inc KCCPPT
Proposal Rcvd. from: GARY KIRMER Company: CLASSIC WELL SERVICE INC Phone: (620) 793-2026

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 08/13/2009 11:15 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK WHERE HAD PREVIOUSLY SANDED PERFS TO AT 2985'. PERFORATE AT 1300', 950', AND 311'. CASING BELIEVED TO HAVE HOLE AT APPROX. 2216'. RUN TUBING TO 2216' AND PUMP 50 SX'S CEMENT. PULL TUBING TO 1315' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 967' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 317' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO BACKSIDE OF 4.5" AND PUMP CEMENT UP TO 300#'S PRESSURE - STOP PUMPING - PRESSURE HELD, SO SHUT IN. USED 170 SX'S TOTAL OF COMMON CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3272 | 3276 | CSG | |

INVOICED
DATE 10-6-09
INV. NO. 2010060334

RECEIVED
AUG 20 2009
KCC WICHITA

Remarks: COPELAND TICKET #C-33049. TIGER WIRELINE #0405.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)