

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-02650-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 26-23S-4W  
330 feet from S Section Line, 330 feet from W Section Line  
Lease Name: GOERING 'A' Well #: 3  
County: RENO Total Vertical Depth: 3588 feet

Operator License No.: 4252  
Op Name: KAHAN AND ASSOCIATES, INC  
Address: PO BOX 700780  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	3568		200 SX
COND	13	485		
PROD	5.5	3553		400

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID M WILSON Company: KAHAN & ASSOC Phone: \_\_\_\_\_

Proposed Plugging Method: PER KCC REGS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/08/2009 3:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:  
APRIL 23 - CASING COLLAPSE AT 2785', SPOTTED 25 SXS PLUG. RAN IN WITH TUBING AND SPOTTED 35 SXS PLUG AT 2708', TAGGED TOP AT 2525', PULLED TUBING TO 550' SPOTTED 100 SXS OF CEMENT, PULLED TO 384' AND CIRCULATED TO SURFACE WITH 75 SXS. JUNE 2-, CUT HEAD OFF TO VISUALLY INSPECTED CONDUCTOR, SURFACE AND PROD., CEMENT DOWN 172' BETWEEN 13" & 8.625", DOWN 155' BETWEEN 8.625' & 5.5", DOWN 30' INSIDE 5.5". RAN 1 INCH IN BETWEEN 13" AND 8.625" AND BETWEEN 8.625" AND 5.5". JUNE 5-, CIRCULATED 130 SXS OF CEMENT THROUGH THE TWO 1 INCH PIPES TO SURFACE.

Perfs:  
**INVOICED**  
DATE: 10-6-09  
INV. NO. 2010060337  
**RECEIVED**  
**AUG 28 2009**  
**KCC WICHITA**

Remarks: APRIL 23RD CEMENT PUMPED BY QUALITY CEMENT, TICKET #3058 JUNE 5TH CEMENT PUMPED COPELAND BURRTON, TICKET #33762.  
Plugged through: TBG

District: 02 Signed: B. J. Hope (TECHNICIAN)