

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20181-00-00
Spot: SWSW Sec/Twnshp/Rge: 32-24S-15W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: SIEBERT Well #: 1
County: STAFFORD Total Vertical Depth: 4300 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3005		
SURF	8.625	250		WITH 285 SX CMT
MSCC		3030		WITH 250 SX CMT
PROD	4.5	4300	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/19/2009 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: RUN TBG TO 2900' & PUMP 15 SX GEL & 40 SX CMT. PULL TBG TO 1000'. CIRCULATE CMT TO SURFACE. PRESSURE TEST 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG W/150 SX CMT

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2009 12:01 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****SQUEEZED @ 723' - 848' W/350 SX CMT. SQUEEZED @ 3378-3407' W/150 SX CMT.**** RAN TBG TO 2900' & PUMPED 11 SX GEL & 40 SX CMT. PULLED TBG TO 1000' & PUMPED 150 SX CMT. CIRCULATED CMT TO SURFACE UP 4 1/2" CASING. PULLED TBG. TOPPED OFF 4 1/2" CASING WITH 13 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH 2 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4180	4184		

INVOICED
DATE 10-6-09
INV. NO. 2010060338

RECEIVED
AUG 31 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

KCC WICHITA

District: 01

RECEIVED

AUG 24 2009

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)