

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20829-00-00
Spot: NWNESE Sec/Twnshp/Rge: 15-19S-7E
2186 feet from S Section Line, 1032 feet from E Section Line
Lease Name: PINKSTON Well #: A1
County: CHASE Total Vertical Depth: 1265 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	63		30 SX
PROD	4.5	1264		150 SX <u>41.11</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/27/2009 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: JAKE KOEHN Company: AMERICAN ENERGIES Phone: (620) 755-2514

Proposed Plugging Method: SAND TO 50' ABOVE PERFS. FILL WITH MUD AND SET A 35 SXS PLUG AT 250' AND FILL TO SURFACE WITH CEMENT.

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 08/27/2009 9:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 1132' AND CAPPED W/4 SXS CEMENT. RAN COILED TUBING TO 450' AND PUMPED 45 SXS TO CIRCULATE TO SURFACE.

GPS: 38.39764, -96.63795

Perfs:

Top	Bot	Thru	Comments
1242	1244		
1211	1213		
1193	1195		2 SPF

INVOICED
DATE 10-7-09
INV. NO. 2010060339

RECEIVED
SEP 03 2009
KCC WICHITA

Remarks: COPELAND CEMENTING TOTAL = 45 SXS 60/40 POZ 4% GEL TICKET #33814

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

1/2

PKT