

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20846-00-00
Spot: E2NESE Sec/Twnshp/Rge: 18-19S-7E
1981 feet from S Section Line, 339 feet from E Section Line
Lease Name: DONAHUE Well #: A-1
County: CHASE Total Vertical Depth: 1291 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	101		50 SX
T1	2.375	1291		
PROD	4.5	1291		150 SX

41-96

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/27/2009 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: JOHN KOEHN Company: AMERICAN ENERGIES Phone: (620) 755-2514

Proposed Plugging Method: SAND TO 50' ABOVE PERFS FILL HOLE WITH MUD & CIRCULATE TO SURFACE FROM 250'

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 08/27/2009 10:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 1152' CAPPED W/4 SXS CEMENT. RAN COILED TUBING TO 450' AND PUMPED 35 SXS TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
1274	1278		W/4 SPF
1248	1251		
1233	1236		

INVOICED
DATE 10-7-09
INV. NO. 2010060339

RECEIVED
SEP 03 2009
KCC WICHITA

Remarks: COPELAND CEMENTING, TOTAL = 35 SXS 60/40 POZ 4% GEL TICKET #33815 38.39729,-96.69126

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

SK

PKT