

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-00887-00-00  
Spot: SESENE Sec/Twnshp/Rge: 22-9S-19W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: BARTOS A Well #: 1  
County: ROOKS Total Vertical Depth: 3589 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	200	0	200 SX
L1	4.5	1700		
PROD	5.5	3580	0	100 SX

116-64

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2009 10:00 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: LOUIS "DON" BOWMAN OR Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Tubing stuck at 2024'.  
Perfed at 1575' and 950'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/27/2009 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:  
Ran tubing to 1875' - pumped 75 sxs 60/40 pozmix - 4% gel with 250# hulls.  
Pulled tubing to 975' - pumped 90 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate to surface.  
Pulled all tubing - pumped 50 sxs 60/40 pozmix - 4% gel.  
S.I.P. 200#.  
Hooked onto 8 5/8". Less than 1/2 barrel - pressured to 200#.

Perfs:  
**INVOICED**  
DATE 10-7-09  
INV. NO. 2010060340

**RECEIVED**  
**SEP 03 2009**  
**KCC WICHITA**

Remarks: QUALITY OIL WELL CEMENTING COMPANY.  
Plugged through: TBG

District: 04 Signed Pat Bedore (TECHNICIAN) CM

SEP 02 2009

PKT

STERLING DRILLING

#1

BARTOS 'A'

22-9-55  
SEISE NE

Contr. STERLING DRLG

ROOKS

Count

E 2161 RBComm.

Comp. 4-1-55

IP 35 BOPD

Tops	Depth	Datum
HEEB	3303	-1112
LANS	3345	-1184
ARB	3577	-1416
TD	3589	-1428

Casing  
8" 200  
5" 3580

DST 3580-86/1 HR; 64' OCM  
600' OCM  
SWB 4 BOPH/4 HR; ACID  
1000; 18 BOPH

JELINEK WEST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS