

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22319-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 29-7S-17W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: SCHRUBEN W Well #: 1  
County: ROOKS Total Vertical Depth: 3350 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1187	0	425 SX
COND	13.38	88		
PROD	5.5	3349	1785	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2009 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: SCHMITT, CARMEN, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2009 1:50 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 2690' with 5 sxs cement - plug on top.  
Shot pipe at 2380' - not free.  
Shot pipe at 1785' - free - pulled to 1758'.  
Quality Oil Well Cementing pumped 150 sxs cement with 200# hulls.  
Pulled pipe to 1200' - pumped 40 sxs cement with 100# hulls.  
Pulled pipe to 675' - pumped 50 sxs cement with 100# hulls.  
Pulled to 150' - pumped 60 sxs cement with 100# hulls - cwc.  
Pulled rest of pipe - hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3254	3268		ARBUCKLE
3131	3178		
3054	3121		
2960	3186		LKC

INVOICED  
DATE 10-7-09  
INV. NO. 2010060341

KANSAS CORPORATION COMMISSION

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

SEP 02 2009  
RECEIVED

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

SEP 01 2009

PRT

ERIC WADDELL COMPANY

P. O. BOX 349

#1 "W" SCHRUBEN

29-7-17W

NE SW NW


NATOMA, KS 67651

CONTR R & C DRILLING, INC.

CTY ROCKS

GEOL

FIELD RIFFE



ELV 1776 KB SPD 3/7/84

CARD ISSUED

7/19/84

IP P 10 BOPD, NW

1771 GL

LKC 3054-3178 OA

LOG	Tops	Depth/Datum
TOP	2706	930
HEEB	2917	1141
TOR	2940	1164
LANS	2958	1182
BKC	3186	1410
MARM	3192	1416
ARB	3253	1477
RTD	3350	1574

API 15-163-22,319

13 3/8 " COND AT 88 / 100SX, 8 5/8 " 1186 / 425SX, 5 1/2 " 3349 / 150SX

DST (1) 3110-3150 (LKC) / 60-60-75-60, (1ST OP) FB, SLOWLY BLDG, (2ND OP) WB, SLOWLY BLDG, REC 120' OCM, SIP 1135-913#, FP 68-78 / 97-97#

DST (2) 3247-3270 (ARB) / 60-45-0-0, (1ST OP) WB, (2ND OP) NB, FLUSH TOOL, NO HELP, REC 20' OCM, ISIP 633#, IFF 58-58#

DST (3) 3270-3300 (ARB) / 35-30-0-0, (1ST OP) WB & DIED IN 35", (2ND OP) NB, REC 10' OIL SPKD MUD, ISIP 633#, IFF 68-68#

MICT - CO, PF (LKC) : 1'3178, 1'3131, 1'3121, 1'3054 AC 4000G (28% INS), SWB LD, GSO, SET 2 7/8 " TBG AT 3240', POP, P 10 BOPD, NW, (GR 37'), 5/9/84

COPYRIGHT 1984  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS