


KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name August Schonhaler Well No. X 2

Location C SW/4 Sec. 30 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3855

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones Drlg.

Address: Wichita, Ks. License No. _____

Operation Completed: Hour 10:45 Day 11 Month 6 Year 1968

The Above well was plugged as follows:

RTD 3855' 8 5/8 csg set at 221' cwc 160 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messer
Well Plugging Supervisor

DATE 6/14/68
INV. NO. 1744-W