

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 94-1

LOCATION SW SW SE

SEC. 30 TWP. 10 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Keller

Operator Birmingham - Bartlett Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3790 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 192' circulated with cement - 5 1/2" at 3783' with 175  
sax cement behind -. Lane Wells plugsto 3527' - perforations  
at 3498'.

Filled with sand to 3480', set 4 sax cement with dump bailer,  
pulled 2800', 5 1/2" - filled with mud to 190', set rock and  
15 sax cement, mud to 30', set rock and 10 sax cement to  
bottom cellar.

**PLUGGING**  
 FILE SEC 30 T 10 R 19W  
 BOOK PAGE 94 LINE 1

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 5-18-53  
 MAY 19 1953  
 CONSERVATION DIVISION  
 Wichita, Kansas

[Signature]  
 District Conservation Agent  
 Date 5-18-53