

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name Keller "H" Well No. 1

Location NW SW NE Sec. 30 Twp. 10 Rge. 19 (E) (W) XX

County Rooks Total Depth 3843

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Garvey Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 10:30P Day 28 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3843' 8 5/8 csg set at 249' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 11/4/68
INV. NO. 8755-11