

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 86-41 Location: NW SE SE  
County: Rooks Sec. 30 Twp. 10 Rge. 19 (E) (W)  
Name of Field or Pool: \_\_\_\_\_ Total Depth: 3758

I have this date completed supervision of plugging of:

Well No. D-1 Lease Keller "D"  
Operator's Full Name Petroleum Inc  
Complete Address: RFD # 2 Great Bend, Kans  
Plugging Contractor: Garvey Drg Co

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 8PM Day 6 Month 3 Year 58

The above well was plugged as follows:

8 5/8" at 216' circulated with cement.  
Gunned pits, circulated hole with heavy mud, set cementing plug at  
550', displaced 20 sax cement through drill pipe, heavy mud to 240',  
set cementing plug and 15 sax cement, heavy mud to 40', set cementing  
plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

3-11-58

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: \_\_\_\_\_  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

This well was supposed to be plugged on 2-28-58 - roads blocked with  
snow - Crews went in on 3-6-58 with cats - cars were unable to get  
through - I was in touch with them by radio.

Reviewed: J. Lewis Brock  
Field Supervisor

Signed: Edon Kelly  
Well Plugging Supervisor

Remarks:

PLUGGING  
3 01 10 R 19 W  
BOOK PAGE 86 LINE 41