

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Texaco, Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name H. Berland "B" Well No. 1

Location NE NE NW Sec. 30 Twp. 10 Rge. 19 (E)    (W) X

County Rooks Total Depth 3815

Abandoned Oil Well X Gas Well    Input Well    SWD Well    D & A   

Other well as hereafter indicated:   

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4 P Day 28 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3815' 8 5/8 csg set at 1631' cwc.

5 1/2 csg set at 3811' cw 75 sc cement.

Filled with sand to 3775' and dumped 5 sc cement with dump bailer

Recov. 2800' of 5 1/2 csg.

Mud to 800' set 10' rock bridge and dumped <sup>20</sup>~~210~~ sc cement.

~~Mud to 250' set 10' rock bridge and dumped 20 sc cement.~~

Mud to 40' set 10' rock bridge and filled to surface with 10 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Mussey  
Well Plugging Supervisor

INVOICED

DATE 4/1/68

INV. NO. 1510-W