

15-163-20221-0000

Form CP-3  
Rev. 6-4-68

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3-17-70  
MAR 17 1970  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Glacier Petroleum Company

Complete Address 1009 Union Center Wichita, Kansas 67202

Lease Name McKenna Well No. 1

Location C <sup>E2</sup> ~~W~~2 NW Sec. 34 Twp. 10 Rge. (E) (W) 19

County Rooks <sup>PT FCC</sup> Total Depth 3762

Abandoned Oil Well ~~XX~~ Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling Co., Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 11A Day 12 Month 3 Year 1970

The above well was plugged as follows:

Total Depth 3762' 8 5/8 csg set at 208' cwc 145 sk.

4 1/2 csg set at 3761' cw 175 sk cmt.

4 1/2 csg perf 3434

Set wood plug at 3300' Poured 30' sd (3300-3270) 5 sk cmt W/dump bailer. (3230-3270)

Cutoff and recovered 2525' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 30 sk gel—70 sk poz 6%—10 sk gel—plug  
and 50 sk poz 6%. Max. pres. 450 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/17/70  
INV. NO. 1600-WSigned: Leo J. Massey  
Well Plugging Supervisor