

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NE NE SE

LOCATION NE-C of the SE 1/4

SEC. 34 TWP. 10 RGE. 19W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

W

I have today completed supervision of plugging of:

Well No. 1 Lease Aksamit AKSAMIT

Operator J. A. Allison Address 716 - Brown Bldg - Wichita

Field _____ County Books

Total Depth 3683 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 169 ft - Circulated with cement
Shib Well was plugged back from bottom to 3379 ft
5 1/2" casing set at 3379 cemented & well tested pressure
line at 3355 ft - Filled hole back from 3379 ft to 3330 ft
with sand - then 5 sacks cement with heavy bitum -
shot off & recovered 2930 ft of 5 1/2" casing - filled with mud
to 260 ft - Plug & 15 sacks cement at 260 ft - Mud to 30 ft of
the surface. Plug & 10 sacks cement -

Jim Baker & Son
Pipe Pullers & Pluggers

C. M. Stough
District Conservation Agent

Date 11-27-47

11-29-47

PLUGGING
FILE SEC 34 T 10 R 19W
BOOK PAGE 2 LINE 5