

15-163-20801-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5-17-78
MAY 17 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163 - 20.801 (of this well)

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Centerm Wichita, Kansas

Lease Name E. C. Casey Well No. 3

Location C SW/4 Sec. 35 Twp. 10 Rge: (E) (W) 19

County Rooks Total Depth 3550'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 4 P Day 16 Month 5 Year 1978

The above well was plugged as follows:

RTD 3550' 8 5/8 csg.set 209' cwc 150 sk. Cmt. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

5-17-78
7322-W

Signed: Leo Massey
Well Plugging Supervisor