

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-42

LOCATION NW NW NE

SEC. 35 TWP. 10 RGE. 19

Dry Hole _____ Abandoned Oil well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-1 Lease Johnson

Operator Sohio Oil Co Address Russell, Kans

Field _____ County Rooks

Total Depth 3518 Feet.

Plugging Contractor Miller Casing Pulling Co

Plugging Contractor's License No. 12

Address _____

(Describe briefly the manner in which the well was plugged)

12 1/2" 120' - 8 5/8" 3332' with 100 sax cement - 7" 3502'

with 65 sax cement behind.

Sand to 3490' set 5 sax cement with dump bailer, pulled

1470' 7" & 750' 8 5/8" - filled with mud to 150', set 25

sax cement, mud to 20', set 15 sax cement to bottom cellar.

PLUGGING
FILE SEC 35 T 10 R 19W
BOOK PAGE 21 LINE 42

RECEIVED
STATE CORPORATION COMMISSION
9-4-53
SEP - 4 1953
CONSERVATION DIVISION
Wichita, Kansas

Edna Letty
District Conservation Agent

Date 9-3-53