

15-163-19093-0000

RECEIVED
STATE CORPORATION COMMISSION
3-2-82
MAR 2 1982

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

CONSERVATION DIVISION
Wichita, Kansas

API Number 15-

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Champion Petroleum

Complete Address Box 9365 - Ft Worth, Texas 76107

Lease Name Suton "A" Well No. 13

Location NW SW SW Sec. 1 Twp. 10 Rge. 20 (East)(West)

County Rooks Total Depth 4037

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Champion Petroleum

Address Box 9365 Ft. Worth, Texas 76107 License No.

Operation Completed: Hour: 2:30 AM Day: 11 Month: 2 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 181' w/175 sb common - 5 1/2" @ 3954 w/400 sb common
1st stage - 250 sb. State-orte poly-mix 2nd stage - 400 sb 2% gel
4% CACL - enc to surf. - hole in casing at 1859' - 2 7/8" tubing @ 1986' -
Ordered 350 sb 50/50 poly-mix 6% gel - 3% CACL, + 12 sb hulls -> pumped
in 50 sb cmt and 12 hulls -> 150 sb, no pressure -> wait 2 hrs on
cmt -> pumped in add. 150 sb cmt - wait 20 hrs. - Ordered 400 sb
cmt, Halcob-lite 6% gel 3% CA-CL; 2 lbs floccul per sb; Pumped in
150 sb - pressure to 400 # P.S.I. wait 20 min - pressure to 400 # Pressure
held - no vacuum check next day - cement to top of 5 1/2" pipe.
Amount of Surface Casing: 181'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICE

DATE: 3-1-82
INV. NO. 0590-1