

15-163-00290-0000

*[Handwritten Signature]*  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
01-02-74  
JAN 2 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name The Gene Brown Company  
Complete Address 1000 SW Second Plainville, Kansas 67663  
Lease Name Coddington Well No. 1  
Location SE SE SE Sec. 2 Twp. 10 Rge. (E) (W) 20  
County Rooks Total Depth 3808'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Chas. Crowe Csg Pulling  
Address Box 706 Hays, Kansas 67601 License No. 733  
Operation Completed: Hour 5:30 P Day 30 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3808' 8 5/8 csg set at 172' cwc 125 sk.  
5 1/2 csg set at 3783 1/2 cw 125 sk cmt.  
5 1/2 csg perf. (3691-3564) & (3423-3414)  
Filled 5 1/2 csg W/sd (3808-3750) dumped 4 sk cmt W/dump bailer. (3750-3720)  
Set 5 1/2 wood plug at 3400' -poured 20' sd -dumped 4 sk cmt W/dump bailer. (3400-3350)  
Cutoff & recovered 1595' of 5 1/2 csg.  
Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk cmt -  
10 sk gel & water -released plug & 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/6/75  
INV. NO. 571-W

Signed: *[Signature]*  
Well Plugging Supervisor