

15-163-02005-0000

Form CP-3
Rev. 6-4-68

KANSAS

19 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8-9-73
AUG 9 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name K & G Oil Company

Complete Address Box 368 Plainville, Kansas 67663

Lease Name Sparks Well No. B-4

Location C N/2 NW SW Sec. 2 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3862'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67663 License No. 683

Operation Completed: Hour 3 P Day 8 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3862' 8 5/8 csg set at 173' cwc 150 sk.

5 1/2 csg set at 3862' cw 125 sk cmt.

5 1/2 csg top perf. (3830')

Filled 5 1/2 csg W/sd (3800-3862) Dumped 5 sk cmt W/dump bailer. (3765-3800)

Cutoff and recovered 870' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls, followed with 100 sk

50-50 poz cmt W/6% total gel. Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Eric F. Murray*
Well Plugging Supervisor

INDEXED

DATE 8/9/73

INV. NO. 9949-W