

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1973 08-09-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name K & G Oil Company

Complete Address Box 368 Plainville, Kansas 67663

Lease Name Sparks Well No. B-5

Location C N/2 N/2 SW Sec. 2 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3889'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 6 P Day 8 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3889' 8 5/8 csg set at 150' cwc 120 sk.

5 1/2 csg set at 3889' cw 125 sk cmt.

5 1/2 csg perf. (3884')

Filled 5 1/2 csg W/sd (3825-3889) Dumped 5 sk cmt W/dump bailer. (3790-3825)

Cutoff and recovered 2000' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water With 500 lbs hulls, --50 sk cmt--

10 sk gel & water--capped with 50 sk cmt by Allied Cementing.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

8/9/73  
7750-W