

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-02115-00-00  
Spot: N2SESE Sec/Twnshp/Rge: 2-34S-5E  
992 feet from S Section Line, 677 feet from E Section Line  
Lease Name: HART Well #: 5  
County: COWLEY Total Vertical Depth: 3160 feet

Operator License No.: 33608  
Op Name: W.D. SHORT OIL CO., LLC  
Address: 102 S RIVER RD PO BOX 729  
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	223		175 SX
PROD	4.5	3139		125 SX <u>102.70</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2009 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: MIKE ANSTINE Company: W D SHORT OIL CO Phone: (316) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 08/14/2009 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

SET CIBP @ 3,075', DUMP BAILED 2 SXS CEMENT ON TOP. PRESSURED TESTED CASING @ 200#, HELD OK. PERFORATED SQUEEZE HOLES @ 275', SWEDGED INTO 4-1/2" CASING, CONSOLIDATED ESTABLISHED CIRCULATION & MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-14-2009 @ 3:30 P.M. CONSOLIDATED CEMENT TICKET #23557.

INVOICED  
DATE 10-14-09  
INV. NO. 2010060385


Remarks: TAGGED CEMENT ON BACKSIDE @ 300'. LAT. 37.11629 - LONG. -96.84445

Plugged through: TBG

RECEIVED  
SEP 10 2009  
KCC WICHITA

District: 02

Signed



(TECHNICIAN)

JK

PBT