

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20852-00-00
Spot: SESW Sec/Twnshp/Rge: 9-17S-25W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: F RUPP Well #: 1
County: NESS Total Vertical Depth: 4452 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	251		WITH 175 SX CMT
PROD	5.5	4444	0	WITH 300 SX CMT <u>144.69</u>

Well Type: EOR UIC Docket No: E17407.1 Date/Time to Plug: 08/14/2009 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: RUN TBG TO 1560' & PUMP 25 SX CMT & 150# HULLS. PERFORATE @ 1200' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE THEN TIE ONTO BACKSIDE & TRY TO PUMP 150 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2009 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

COMPANY HAD SQUEEZED WELL @ 1586' WITH 150 SX CMT. WHILE DRILLING OUT THEY DRILLED UP CASING, SHUT DOWN & DECIDED TO PLUG THE WELL.
RUN TBG TO 1560 & PUMP 25 SX CMT. PRESSURE CASING & HELD AT 500#.
PERFORATED @ 1200'. RUN TBG TO 1250' & PUMPED 140 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & PUMPED 80 SX CMT. PRESSURED TO 500# & HELD. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4445	4453		OH

INVOICED
DATE 10-13-09
INV. NO. 2010060372

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 17 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
SEP - 9 2009
KCC DODGE CITY

Form CP-2/3