

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22688-00-00  
Spot: SESESW Sec/Twnshp/Rge: 5-22S-11W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SLEEPER Well #: 1  
County: STAFFORD Total Vertical Depth: 3590 feet

Operator License No.: 4656  
Op Name: DAVIS PETROLEUM, INC.  
Address: 7 SW 26 AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	310		
PROD	4.5	3589	1011	WITH 140 SX CMT 116.68

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2009 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3530'. PLUG AT 600' WITH 40 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. 10 SX GEL.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/04/2009 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3420' & 4 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 325' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3478	3501		

RECEIVED  
SEP 14 2009  
KCC WICHITA

INVOICED  
DATE 10-13-08  
INV. NO. 2010060373

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

Richard N. Lacey  
(TECHNICIAN)

RECEIVED  
SEP - 9 2009  
KCC DODGE CITY