

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19143-00-00
Spot: SENESE Sec/Twnshp/Rge: 14-17S-4E
1509 feet from S Section Line, 334 feet from E Section Line
Lease Name: KNIGHT Well #: 1
County: MARION Total Vertical Depth: 2350 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		
PROD	5.5	2316	1218	76-38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/27/2009 9:20 AM KCC Agent: SHANE JONES

Actual Plugging Report:

7/09 KELSO PULLED TUBING AND RODS, SANDED OFF BOTTOM TO 2250' & CAPPED W/5 SXS CEMENT. SHOT OFF CASING AT 1218' AND PULLED CASING. 7/24/09 TRIED PLUGGING BUT PVC WOULD NOT HOLD TOGETHER LOST APPROX 60' TO 1" SCHD 40 PVC IN THE HOLE. IT WAS DECIDED TO SHUT DOWN AND COME BACK IN MONDAY WITH A NEW PLAN. 7/27/09 COPELAND CEMENT DOING TOP PLUG. RAN 1.25" POLY SPOOL IN THE HOLE TO 260'. THEY CIRCULATED 110 SXS OF 60/40 POS W/4% GEL TO THE SURFACE. THEN PULLED THE PLY BACK OUT OF THE HOLE. 7/28/09 CHECKED TOP PLUG 240' DOWN TO PLUG AND FOUND FLUID @ 70'. PLUG HAS FELL APPROX 25' BELOW SURFACE CASING. 7/29/09 COPELAND CEMENTING OUT REDOING TOP PLUG. THEY RAN POLY LINE DOWN TO APPROX 250' AND CIRCULATED 90 SXS 60/40 POSMIX W/4% GEL TK #33039. 7/30/09 CHECKED CEMENT WITHIN 4' OF SURFACE.

Perfs:

INVOICED
DATE 10-13-09
INV. NO. 2010060378

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)