

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19145-00-00

Spot: SESWSW

Sec/Twnshp/Rge: 13-17S-4E

331 feet from S Section Line, 4081 feet from E Section Line

Lease Name: MCCOY

Well #: 2

County: MARION

Total Vertical Depth: 2359 feet

Operator License No.: 31528

Op Name: KELSO, MIKE OIL, INC.

Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		
PROD	5.5	2322		

76.67

Well Type: OIL

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: KCC

Company:

Phone: (620) 562-8088

Proposed
Plugging
Method:

AS PER KCC

Plugging Proposal Received By:

WitnessType: PARTIAL

Date/Time Plugging Completed: 07/24/2009 11:00 AM

KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

7/09 KELSO PULLED TUBING AND RODS, SANDED OFF BOTTOM TO 2275' & CAPPED W/5 SXS CEMENT. SHOT OFF CASING AT AND PULLED CASING.
7/24/2009 COPELAND CEMENT DOING TOP PLUG. RAN 13 @ 20' STICKS OF 1" SCHD 40 PVC IN THE HOLE. THEY STARTED PUMPING CEMENT AND PVC BROKE OFF AT THE GROUND. THEY THEN RAN 13 MORE STICKS OF PVC TO APPROX 260;' AND CIRCULATED 100 SX OF 60/40 POS W/4% GEL TO THE SURFACE. THEN PULLED 1" PVC OUT TO USE ON THE NEXT HOLE. 7/28/2009 CHECKED TO PLUG 150' DOWN TO PLUG 60' TO FLUID. 7/29/2009 COPELAND OUT TOPPING OFF WELLS USED 30 SXS TK #33038. 7/30/2009 CHECKED CEMENT, CEMENT @ SURFACE.


INVOICED
DATE 10-13-09
INV. NO. 20100 60378

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 17 2009
CONSERVATION DIVISION
WICHITA, KS