

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20211-00-00
Spot: ^{NW} NENW Sec/Twnshp/Rge: 13-19S-4E
4625 feet from S Section Line, 3344 feet from E Section Line
Lease Name: FIREBAUGH Well #: 1
County: MARION Total Vertical Depth: 2340 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	200		140 SX
PROD	4.5	2340	1017	65 SX

76.05

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KCC Company: _____ Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/29/2009 12:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

7/28/2009 KELSO'S PULLING RODS AND TUBING. THEY SANDED OFF BOTTOM TO 2200' AND CAPPED WITH 5 SXS CEMENT. THEY SHOT OFF CASING @ 1017' AND STARTED PULLING CASING. 7/29/2009 COPELAND RAN POLY LINE DOWN TO APPROX 260' AND CIRCUALTED 90 SXS OF 60/40 POS W/4% GEL TO SURFACE. TK #33039. 7/30/09 CHECKED TOP PLUG. CEMENT DONE 75', NO FLUID IN HOLE. I CONTACTED MIKE KELSO. MIKE WANTING TO KNOW SINCE WELL IS DRY COULD HE SLURRY IT TO TOP IF OFF. I SPOKE TO JEFF KLOCK AND IT WAS APPROVED. 8/24/09 SPOKE TO MIKE KELSO THIS MORNING GOING TO TOP OFF WELL TODAY.

Perfs:

Top	Bot	Thru	Comments
2270	2328		

INVOICED

DATE 10-13-09

INV. NO. 2010060378

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2009

Remarks:
Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed _____



(TECHNICIAN)

JK

PG