

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20305-00-00
Spot: SWNENE Sec/Twnshp/Rge: 26-17S-4E
4230 feet from S Section Line, 963 feet from E Section Line
Lease Name: HAEFNER Well #: 3
County: MARION Total Vertical Depth: 2393 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210		175 SX
PROD	4.5	2970	1200	125 SX <u>77.77</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/27/2009 10:30 AM KCC Agent: SHANE JONES

Actual Plugging Report:

7/09 KELSO PULLED TUBING AND RODS, SANDED OFF BOTTOM TO 2300' & CAPPED W/5 SXS CEMENT. SHOT OFF CASING AT 1200' AND PULLED CASING . 7/27/09 COPELAND CEMENT DOING TOP PLUG. RAN 1.25" POLY SPOOL IN THE HOLE TO 260'. THEY CIRCULATED 80 SXS OF 60/40 POS W 4% GEL TO THE SURFACE. THEN PULLED THE POLY BACK OUT OF THE HOLE. 7/28/09 CHECKED TOP PLUG 75' DOWN TO PLUG AND FOUND FLUID @ 50'. 7/29/09 COPELAND OUT TOPPING OFF WELLS WITH POLY TRAILER, 35 SXS TK #33038. 7/30/09 CHECKED CEMENT, CEMENT @ SURFACE.

Perfs:

INVOICED
DATE 10-13-09
INV. NO. 2010060378

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)