

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21030-00-00
Spot: NENENW Sec/Twnshp/Rge: 25-27S-34W
125 feet from N Section Line, 2618 feet from W Section Line
Lease Name: WARD SWD Well #: 1
County: HASKELL Total Vertical Depth: 1565 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	4.5	967	0	WITH 450 SX CMT
COND	8.625	60		WITH 50 SX CMT
PROD	2.375	1562		WITH 200 SX CMT

Well Type: SWD UIC Docket No: D27332.0 Date/Time to Plug: 08/19/2009 4:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

50.86

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2009 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 35 SX CMT & 100# HULLS INTO PERFS @ 1462'. FILLED 2 3/8" TBG.
PRESSURE TO 300 PSI. PUMP 15 SX CMT INTO 2 3/8" X 4 1/2" ANNULUS.
PRESSURED TO 150 PSI. PUMP 20 SX CMT INTO 4 1/2" X 8 5/8" ANNULUS.
PRESSURE TO 150 PSI.

Perfs:

Top	Bot	Thru	Comments
1462	1562		

RECEIVED
SEP 21 2009
KCC WICHITA

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

DATE 10-19-09
INV. NO. 2010060392

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP 10 2009
KCC DODGE CITY

FORM CP-2/3