

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20082-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 16-31S-39W
1250 feet from S Section Line, 2420 feet from E Section Line
Lease Name: DANIELS GU A Well #: 2
County: MORTON Total Vertical Depth: 2932 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	611		WITH 400 SX CMT
PROD	5.5	2932	0	WITH 475 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/11/2009 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: RIH W/TBG TO 1580'. PUMP 25 SX CMT. PERFORATE @ 630-0'. CIRCULATE CMT TO SURFACE.

95.29

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2009 1:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

TBG FISH IN HOLE TOP @ 1580'. PUMP 25 SX CMT & 100# HULLS @ 1575'.
PERFORATE 5 1/2" @ 630'. RIH W/TBG TO 630' & PUMP 80 SX CMT. CIRCULATE TO
SURFACE. POOH W/TBG. TIE ONTO 5 1/2" & PUMP 100 SX CMT. CIRCULATED 5
1/2" X 8/58" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2696	2912		

RECEIVED
SEP 21 2009
KCC WICHITA

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

DATE: 10-19-09
INV. NO. 2010060392

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP 10 2009
KCC DODGE CITY

Form CR 2/3