

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-24010-00-00
Spot: SWSWSWSE Sec/Twnshp/Rge: 12-34S-13E
165 feet from S Section Line, 2475 feet from E Section Line
Lease Name: DALBY Well #: 1 (CS7)
County: MONTGOMERY Total Vertical Depth: 1929 feet

Operator License No.: 33874
Op Name: CUSTER OIL & GAS, LLC
Address: JCT HWY 123 & HWY 11 PO BOX 628
BARNSDALL, OK 74002

62.69

Well Type: SWD UIC Docket No: D20381.0 Date/Time to Plug: 09/09/2009 10:00 AM

Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 100' at 1870', 50' at 800' and 350' to surface

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2009 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" tubing to 1870' gelled hole and pumped 30 sacks of 60/40 pozmix with 4% gel. Pulled up to 815' and pumped 10 sacks. Pulled up to 405 and circulated cement to surface. Pulled 2" and topped well off. A total of 65 sacks of cement were used to plug this well.

Perfs:

RECEIVED
10-19-09
2010060394

RECEIVED
KCC DISTRICT #3
SEP 15 2009 DAS
CHANUTE, KS


RECEIVED
KANSAS CORPORATION COMMISSION
SEP 21 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

