

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19044-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 15-14S-14W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BOXBERGER A Well #: 1
County: RUSSELL Total Vertical Depth: 3266 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3088		
SURF	8.625	505	0	w/unknown sxs cmt <u>106.15</u>
PROD	5.5	3265	0	w/unknown sxs cmt

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/11/2009 12:30 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (316) 772-6449

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 6 sxs gel.
Perfs: 1450' - 835' - 480'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2009 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2950' - pumped 6 sxs gel - followed with 100 sxs cement with 300# hulls.
Pulled tubing 1500' - pumped 150 sxs cement with 300# hulls mixed in - cement circulated.
POOH. Hooked to casing - pumped 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 350#.
Hooked up to Braden head and pumped 2 sxs cement at 300#.

Perfs:

Top	Bot	Thru	Comments
3036	3041		
3023	3029		
3001	3012		
2892	3896		
2882	2886		
2269	2300		150 SX

RECEIVED
SEP 21 2009
KCC WICHITA

INVOICED
DATE 10-19-09
INV. NO. 2010060391

Remarks: ALLIED CEMENTING COMPANY-TICKET #38416.
Plugged through: TBG

District: 04 Signed Ray A Dinkel (TECHNICIAN) CM

SEP 15 2009