

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22235-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 34-13S-20W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: STORM J Well #: 6
County: ELLIS Total Vertical Depth: 3836 feet

Operator License No.: 5285
Op Name: HANSEN, DANE G. - TRUST
Address: PO BOX 187
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	306	0	w/160 sxs cmt
PROD	5.5	3825	0	w/175 sxs cmt

124.67

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2009 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICHARD WALLGREN Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered 420 sxs 60/40 pozmix - 4% gel - 500# hulls.
Alt II at 1520' w/375 sxs. CIPB at 3400' and 3460'.
Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2009 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin Drilling RIH with tubing to 3255'. Swift Cementing rigged to tubing and pumped 150 sxs cement with 200# hulls mixed in.
Pulled tubing to 2050'. Swift Cementing rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in.
Pulled tubing to 1050'. Swift Cementing rigged to tubing and pumped 100 sxs cement with 100# hulls to circulate cement to pit.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Rigged to 8 5/8" casing and pumped 10 sxs cement.
Max. P.S.I. 200#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3825	3836	OH	Arbuckle

RECEIVED
SEP 21 2009
KCC WICHITA

INVOICED

Remarks: SWIFT CEMENTING COMPANY-TICKET #16151.

Plugged through: TBG

DATE: 10-19-09
INV NO. 2010060395

District: 04

Signed [Signature]
(TECHNICIAN)


CM

[Handwritten mark]

THE DANE G. HANSEN TRUST #6 J. STORM 34-13-20W
 P.O. BOX 187 LOGAN, KS 67646 NW SW NE
 CONTR C-G DRILLING CO. CTY ELLIS

GEOL JERRY JESPERSEN FIELD PLEASANT

E 2253 KB CM 1/12/81 CARD ISSUED 4/9/81 IP OIL WELL
 ARB OH 3825-3836



API 15-051-22,235

SMP	TOPS	DEPTH	DATUM
ANH		1547	+ 706
TOP		3220	- 967
HEEB		3474	-1221
TOR		3494	-1241
LANS		3512	-1259
B KC		3798	-1545
MARM		3802	-1549
CONG		3816	-1563
ARB		3824	-1571
RTD		3836	-1583

8 5/8" 306/160sx; 5 1/2" 3825

- DST (1) 3421-3456/15-45-60-45, REC 305' GMCO, 305' GMW, SIP 1229-1197#, FP 105-116/127-264
- DST (2) 3540-3560/15-45-30-45, REC 320' SOGCMW, SIP 508-508#, FP 84-116/137-190#
- DST (3) 3561-3600/15-45-60-45, REC 970' HO & GCM, SIP 812-781#, FP 102-195/226-380#
- DST (4) 3618-3665/15-45-60-45, REC 60' OCM, 180' MWCO, SIP 905-864#, FP 52/161#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

(OVER)

THE DANE G HANSEN TRUST #6 J. STORM 34-13-20W
 NW SW NE

- DST (5) 3645-3665/15-45-30-45, REC 20' M, SIP 286-74#, FP 42-92/42-42#
 - DST (6) 3672-3687/15-45-60-45, REC 20' HOCM, SIP 596-504#, FP 30-51/61-123#
 - DST (7) 3691-3712/15-45-60-45, REC 90' MW, SIP 665-623#, FP 52-63/52-83#
- MICT - CO, (ARB OH), POP, OIL WELL - POTENTIAL NOT AVAILABLE