

4-041780 15-163-02011-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

7-24

API Number: 15- - 5-25-57

SE SW NW /4 SEC. 03, 10 S, 20 W
2970 feet from S section line
4290 feet from E section line

Operator license# 5363

Lease: Nutsch Well # B-2

Operator: Berexco, Inc.

County: Rooks

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3807 ^{123.72} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 243 feet
w/150 sxs.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:30 P.M. Day: 24 Month: July Year: 1996

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: 5 1/2" casing set at 3805' w/150 sxs cement. Perf. at 3578' - 3699'.
Ordered 275 sxs. 60/40 pozmix -10% gel - with 1/4# F.C. plus 500# hulls and 15 sxs gel.
Squeezed at 1130' with 200 sxs - 1380' to 1450' with 75 sxs - 1580' with 50 sxs - 1248' with
70 sxs. Remove packer at 3565'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour 5:30 P.M., Day: 24, Month: July, Year: 1996

Actual plugging report: R.I.H. with tubing 3805' - spotted 15 sxs gel, followed with 50 sxs
cement with 300# hulls. Pulled tubing to 1800'. Circulated cement to surface with 140 sxs
cement and 200# hulls. P.O.O.H. with tubing. Squeezed casing with 15 sxs cement. R.U.
cementers to 8 5/8" S.P. Squeezed annulus with 75 sxs cement and hulls. Max. P.S.I. 500#.
S.I.P. 200#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2239 GL

I did / did not observe the plugging
RECEIVED
ANNIS L. HAMEL
(agent)

INVOICED
DATE AUG 06 1996
WIC. NO. 46169
7-24

AUG 05 1996
8-5-96
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3