

4-071166

15-163-02016-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

1-23

API Number: 15- - 2-5-51

NW SE SE /4 SEC. 04, 10 S, 20 W
990 feet from S section line
990 feet from E section line

Operator license# 5363

Lease: Glick Well # 6

Operator: Berexco, Inc.

County: Rooks

Address: P.O. Box 723
Hays, Kansas 67601
Ted Crawford

Well total depth 3805 ^{123.66} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 109 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing - O.W.S. License#

Address: Russell, Kansas 67665 - Plainville, Kansas 67663

Company to plug at: Hour: A.M. Day: 23 Month: January Year: 1996

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

RECEIVED
KANSAS CORP
JAN 30 1996
1-30-96

Were: 8 5/8" - 109' S.P. cwc. w/90 sxs cement. 5 1/2" casing set at 3802' w/80 sxs cement. 5 1/2" casing squeezed from 936' to 1501' and 3425' with 975 sxs total cement. Any. 1710'. Small hole in casing. Proposal 375 sxs 60/40 pozmix - 10% gel - 5 sxs hulls. Pump in with pump truck. Spotted and displace all cement through tubing. With tubing load 5 1/2" casing from bottom to top with cement - squeeze and shut in under pressure. Squeeze 5 1/2" x 8 5/8" annulus with cement.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 5:30 P.M., Day: 23, Month: January, Year: 1996

Actual plugging report: Berexco, Inc. ordered 375 sxs 60/40 pozmix - 10% gel and 5 sxs hulls. Pumped in with pump truck - spotted and displaced all cement through tubing.
1) 2 3/8" tubing at 3778' w/100 sxs cement and 3 sxs hulls - spotted and displace.
2) 2 3/8" tubing at 2335' w/100 sxs cement - spotted and displaced.
3) 2 3/8" tubing at 885' w/70 sxs and w/2 sxs hulls cement circulated out of 5 1/2" casing.
4) Squeezed 5 1/2" x 8 5/8" casing with 20 sxs cement. Max. P.S.I. 400#. S.I.P. 100#.
5) Squeezed 5 1/2" x 8 5/8" annulus with 85 sxs cement. Max. P.S.I. 150#.

Remarks: Cemented by Allied.
Condition of casing(in hole): GOOD BAD Any.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] did not [] observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE JAN 30 1996
INV. NO. 44762